SCHEDULE.

Sl. No.	Items of work	Unit	Quantity	To conform to Specification No.
	(1) *Deviation of Line between Miles* 273/18 *and* 274/12.			
1	Jungle clearing ...	Sqr.	48	Specification of Works, Mysore Railways, 1912 Edition.
*2	Earthwork, forming bank 0 to 7 feet high ..	1,000 C.ft.	36,000	
3	Earthwork, in cutting in all soils including blasting, if any.	,,	15,800	Do
4	Earthwork excavating side drains in all soils including rock, if any.	,,	6,400	Do
5	Earthwork excavating catch water drains ..	,,	7,800	Do
6	Excavating channels in Railway limits in all soils including blasting rock, if any.	,,	30,000	Do
7	Rough stone revetment with jelly backing ..	100 C.ft.	1,300	Marryat's Specification No. 42.
8	Collection of gravel ballast in stacks 2" per ft. to be height of heaps, which will be of one or more units.	1,000 C.ft.	29,000	
	(2) *Constructing* 2-20' *Girder Bridge at Mile* 274/1-2.			
1	Earthwork excavation of founds in all soils including blasting rock, if any.	,,	9,600	Marryot's Specification No.
2	Concrete broken stone in surki mortar ...	100 C.ft.	4,200	Do 18(a)
3	Coursed rubble 1st sort in surki mortar ...	,,	9,520	Do 33
4	Pointing with cement ...	100 S.ft.	2,700	Do 58
5	Cement concrete bed blocks including cost of frame work complete.	C.ft.	35	Do 20
6	Burnt stone slabs 6' thick one line dressed champhered and fixed in mortar.	S.ft.	368	Do 29
7	Hoisting and fixing Railway girders including riveting, fixing bracings, etc., complete.	Ton	7·34	
8	Painting girders with Siderosthen Anti-corrosive Paint, two coats.	100 S.ft.	800	Do 129
9	Rough stone revetment with jelly backing ...	100 C.ft.	6,100	Do 42

Remarks.—* Will be paid by section measurements deducting for shrinkage 2" per foot of height of bank.

Note :—The intending Contractors may quote for both or either of the works.

R. N. MIRZA,
Senior Executive Engineer.

MYSORE PUBLIC WORKS DEPARTMENT.

FORM OF ADVERTISEMENT.

Notification, dated the 7th February 1933.

Notice is hereby given that sealed tenders will be received at the Office of the Executive Engineer, Shimoga Division, up to 27th February 1933, for maintenance work of Kubatur Urumundinakere, Regd. No. 116 and 134, Sorab Taluk.

An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of June 1933.

2. The plans, detailed estimate and conditions may be seen at the Executive Engineer's Office, at Shimoga, between the hours of 11 A.M. and 5 P.M.

3. Tenders should be submitted on printed forms which may be obtained from the Executive Engineer. The tenders should be accompanied by a statement in the form given below, showing the rates in figures and words at which the different items specified will be executed.

4. Each tender must be accompanied by a deposit of Rupees one hundred and fifty only in cash or Government Promissory Notes, as earnest money, and be superscribed "Tender for maintenance work of Kubatur Urumundinakere, Sorab Taluk" in default of which, tenders will be rejected.

5. The final acceptance of any tender will rest with the Executive Engineer who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within eight days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond, in default of which, his tender will be considered cancelled, and his earnest money will be forfeited.

7. The name of the successful competitor, whose tender has been accepted, will be posted on the Notice Board in the Executive Engineer's Office in due course. No enquiries regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

9. Percentage rates will not be considered.

10. No claims for enhanced rates will be entertained on any account after acceptance of tenders.

11. For all Lump sum provisions and unforeseen items found necessary during execution detail measurement will be taken and current schedule rates will be paid.

12. The accepted tenderer is bound to execute the work as per his bond and to receive payment to the extent of grant sanctioned.

13. In all matters of the disputes regarding quality of the work and rates, the decision of the Superintending Engineer, Shimoga Circle is final and legally binding.

Abstract estimate for maintenance work of Kubatur Urumundina Doddakere Regd. Nos. 116 & 134 of Sorab Taluk.

No.	Items of work	Unit	Rate Rs.	a.	p.	Quantity	Cost
1	Earthwork to bund levelling watering and consolidation including lift and lead of ¾ mile.	Cyd.				3,758	

G. SESHAGIRI RAO,
Executive Engineer.

MISCELLANEOUS DEPARTMENTS.

OFFICE OF THE SUPERINTENDENT, BANGALORE PALACE, BANGALORE.

Tender Notice, dated 10th February 1933.

Notice is hereby given that sealed tenders will be received at the Office of the Superintendent, Bangalore Palace, upto Monday the 27th February 1933, till 3 P.M., for collecting metal chips from the mounds and heaps formed around the big pit (old Quarry) near Beaufort and the Granite near Bangalore Palace.

Each tender must be accompanied with a deposit of "Rupees twenty-five" in cash as earnest money, in default of which tenders will be rejected.

The acceptance of any tender will rest with the Huzur Secretary to His Highness the Maharaja, who does not bind himself to accept the lowest or any tender or to assign any reason whatsoever for the rejection of any tender.

The list of successful tenderers, will be posted on the notice board in the Office of the Superintendent, Bangalore Palace in due course.

Within eight days of the acceptance of the tender the successful tenderer will be required to pay the full amount of the tender and to execute the required agreement, in default of which the tender will be considered cancelled and his earnest money forfeited.